Offers high level of free cooling, Factory fitted solution (Mega-Bay)

Efficiency in combination with Liquid Cooled Chillers

Plug & play solutions

Kelvion • All rights reserved • Subject to changes • Version 02 • 10/25



**Kelvion Heat Rejection & Heat Recovery** 

# MEGA-BAY® & GIGA-BAY® DRY COOLING SYSTEMS



#### **OVERVIEW**

- ▶ Fast quote & project delivery
- ▶ Suited for large scale applications > 20MW
- ► In the intent of API661 (robustness & maintainability)
- ▶ On stock materials
- ▶ Increased capacity per bay → Fewer modules
- ▶ Small number & long-life fans
- ► Flexible HX construction, with mounting structure included
- ► Pumps and other components fitted / selected and supplied separately



## **SINGLE TUBE**

- ► Steel tube with high performance groovy alu fins
- ▶ Tubes welded or expanded into header
- ▶ Manufacturable tube length: 18m
- ▶ Prismatic plug headers for tube access

## **MARKETS**



**Data Center** 





/AC Hydro

	MEGA-BAY	GIGA-BAY
Footprint per MW	••••	••••
Power consumption	●●●○○	●●○○○
On site errection work	●●○○○	••••
Maintenance	●0000	●0000
Expected delivery time	••••	••••
Height above ground	●●●○○	••••

#### MEGA-BAY®



- ► Capacity per bay: 1,5 4 MW
- ▶ Plug & play with foldable legs
- ▶ Fan sizes: 14 ft
- ▶ Factory or site assembled
- ► Modular design
- ► Maintenance platforms
- ► FEA and structural calculation applied



#### **GIGA-BAY®**

- ► Capacity per bay: 4 8 MW
- ▶ Large duties
- ▶ Fan sizes: 22 ft
- ▶ Site assembled
- ► Modular design
- ▶ FEA and structural calculation applied